

PROJECT PROFILE



PROJECT TYPE


UPS / Datacenter

PROJECT LOCATION

Kansas City, MO

PRODUCTS & SERVICES

Battery Replacement
Battery Removal & Recycling
Battery Monitoring Installation &
Commissioning



Project Details

This downtown Kansas City datacenter had two strings of batteries (80 jars total) that were no longer able to support their UPS load. API was contracted to remove and replace these 80 batteries.

EnerSys 12HX-400FR valve-regulated lead acid batteries (VRLA) were used as the replacement cells.

After the battery replacement was complete, an Alber BDS-40 battery monitoring system was installed and commissioned.



Contract Holder
Contract GS-07F-0668N



COMPLETE BATTERY SOLUTIONS

www.apibattery.com