

# PROJECT PROFILE



**PROJECT TYPE**  
Utility / Substation

**PROJECT LOCATION**  
LaCygne, KS

**PRODUCTS & SERVICES**  
Battery Removal & Recycling  
Battery Installation  
Charger Installation



## Project Details

This public power utility contracted API to provide a turnkey solution to remove their old battery system and install a new one.

The existing racks were used, but a new charger was supplied. The client also requested that we supply a temporary 120v VRLA battery string to carry the load during the changeout.

After installation and prior to transitioning to the new battery, an inspection was conducted per IEEE-450 guidelines (voltage, internal resistance, specific gravity).

The old batteries were de-commissioned and properly disposed of.



Contract Holder  
Contract GS-07F-0668N



COMPLETE BATTERY SOLUTIONS

[www.apibattery.com](http://www.apibattery.com)